



2008-10-28, Tongli

Research Center of Laser Fusion CAEP

ICUIL2008



Recent Progress of SG-III Laser Facility and its Prototype

Wanguo Zheng

Research Center of Laser Fusion of
CAEP

P.O.Box 919-981, Mianyang, China, 621900. Fax: 86-0816-2491410,

Email:wgzheng_caep@sina.com


Outline



Research Center of Laser Fusion CAEP



- ◆ Introduction
- ◆ Design of SG-III Laser Facility
- ◆ Status of SG-III Project
- ◆ Summary



Outline



Research Center of Laser Fusion CAEP




◆ Introduction

◆ Design of SG-III Laser Facility

◆ Status of SG-III Project


◆ Summary



Introduction – Plan of developing ICF drivers in China



Research Center of Laser Fusion CAEP




Introduction – Prototype of SG-III



Research Center of Laser Fusion CAEP



Function 1: The main test bed to validate the key technology applied in SG-III.





Introduction – Specifications of Prototype of SG-III

Research Center of Laser Fusion CAEP



Specifications:

- (1).Beam number: 8 (4×2)
- (2).Beam aperture: 290mm×290mm
- (3).Wavelength: 0.351 μ m
- (4).Energy:
 - 1.2kJ/1ns/0.35 μ m/beam
 - 1.8kJ/3ns/0.35 μ m/beam
- (5).Temporalshape: 1.0ns~3.0ns
- (6).Beam divergence : 70 μ rad (95%energy enclosed)
- (7).Pointing: 30 μ m(RMS, $f=2.2m$)
- (9).Energy spread: 10%(RMS)



Introduction – Key units in Prototype of SG-III




Research Center of Laser Fusion CAEP


Energy bank




Disk amplifier



Spatial filter



Final optical assembly



PEPC

Deformable mirror

Preamplifier

Front End





Introduction – Performance of Prototype of SG-III

Research Center of Laser Fusion CAEP



Energy







Introduction – Performance of Prototype of SG-III

Research Center of Laser Fusion CAEP




Beam quality: Far field and near field of 3 ω



Farfield quality evaluation

Date : 2007/09/20 17:51:32 N1
D= 290mm f=4000mm
1DL : 2.42 μ rad (@351nm)
 $\Phi_{70.0\%}$: 42.6 μ rad ~ 17.6DL
 $\Phi_{81.3\%}$: 52.7 μ rad ~ 21.7DL
 $\Phi_{90.1\%}$: 65.0 μ rad ~ 26.8DL
 $\Phi_{95.0\%}$: 77.4 μ rad ~ 31.9DL
Sr=0.004547
Energy : 589J/1ns/351nm

About 30DL (95%energy enclosed)



Modulation of near field is about 2.2




Introduction – Performance of Prototype of SG-III


Research Center of Laser Fusion CAEP



Temporal shape



Shaped pulse



Pulse width :1.1ns, Average energy:939J





Introduction – Performance of Prototype of SG-III

Research Center of Laser Fusion CAEP




Pointing

Experiment shows the pointing accuracy can reach 25um(RMS,f=2.2m)



Pointing image in degree 1



Pointing image in degree 2

Distribution of the 8 focal spots in the LEH captured by X-ray pinhole camera.
(100J/0.25ns/beam)

Outline



Research Center of Laser Fusion CAEP




◆ Introduction

◆ Design of SG-III Laser Facility

◆ Status of SG-III Project


◆ Summary





Design of SG-III Laser Facility – Overview

Research Center of Laser Fusion CAEP




Three function area: 1. Laser hall, 2. Optical Assembly Building, 3.Target area

Area size: 172.8m × 76m



Design of SG-III Laser Facility – Overview

Research Center of Laser Fusion CAEP






Design of SG-III Laser Facility --- Laboratory

Research Center of Laser Fusion CAEP



Lab area : $176m \times 76m$

SG lab. is divided into three parts: laser system area, target experiment area and cleaning assembling area.





Design of SG-III Laser Facility – Specifications

Research Center of Laser Fusion CAEP




- ✓ Beams number: 48 (4×2-6)
- ✓ Beam Size: 360mm×360mm
- ✓ Wavelength: 351nm
- ✓ Energy: 180KJ @3ns flat top pulse
- ✓ Temporal shape: arbitrary shape
- ✓ Beam quality: 10DL enclosed 95%Energy
- ✓ Beam spectrum: 0.1nm~1.2nm
- ✓ Power Balance: 10% RMS (foot)
- ✓ Pointing: 30um RMS (f=4,000mm)

SG-III Laser Facility ----System distribution



Research Center of Laser Fusion CAEP




Characters:

【basic rule】 “Pulse with same character in one cone and adjustable among different cone”

【Method】 “One bundle corresponding to one cone on target chamber”

Schematic of one of the 48 beamlines in the SG-III facility





FD: Front-end
 PAM: Preamp module
 AMP: Amplifier
 SF: Spatial filer
 CM: Cavity mirror
 DM: Deformable mirror
 PA: Pole array
 BR: Beam reverser
 PC: Pockel cell
 PMU: Parameter measurement unit
 FCU: Frequency convert unit
 WFL: Wedged focus lens
 BSG: Beam sampling grating
 CPP: Continuous phase plate
 TM: Transport mirror
 DS: Debris shield





SG-III Laser Facility ----Fluence distribution

Research Center of Laser Fusion CAEP




SG-III laser facility optimization design and disks distribution.



Design of SG-III Laser Facility – Optical layout



Research Center of Laser Fusion CAEP



- The multi-pass architecture that is common to all of the 48 beamlines of SG-III.
- Pulse is Injected from CSF and the beam reverser is located in TSF. There are four passes through the main amplifier and three passes through the power amplifier.
- Deformable mirror with large aperture located in CM to compensate the waveform distortion.

Design of SG-III Laser Facility –Main amplifier



Research Center of Laser Fusion CAEP




Specifications	SG-III	NIF	LMJ	备注
Total disk	16	18	18	
Disk configuration	9+7	11+7	9+9	
Equivalent disk	57	58	72	
Total gain length of disk	273cm	277cm	344cm	Disk thickness: 4cm
Length of main amplifier	~112m	~ 123	~ 101m	From to CM L4
Injecting method	CSF farfield injecting	TSF farfield injecting	TSF farfield injecting	
Injecting energy	<1J	~several hundred mj	~several hundred mj	
Beam aperture in main amplifier	275mm,320mm	360mm	360mm	
Beam aperture in booster amplifier	309mm,350mm	360mm	360mm	
Filling factor in booster amplifier	76%	81%	81%	
Beam aperture in reverser	72mm	–	?	
Vignetting allowance [*]	50mm	35mm	?	
Fluence on Pickoff mirror	~4J/cm ²	–	?	




Design of SG-III Laser Facility – Optical layout of main amplifier



Research Center of Laser Fusion CAEP



- Different beam size in 1-2 pass and 3-4 pass to mitigate effect on beam quality from the static wavefront distortion of the edge of laser glass.
- Image relay design
- Low fluence on Pick-off mirror to ensure the system work stably.







Design of SG-III Laser Facility – Optical Layout of Reverser



Research Center of Laser Fusion CAEP






Rotate the beam in beam reverser before 3-pass the main amplifier, the stigmatism caused by thermal distortion of laser glass can converted to defocus. Therefore beam quality can be improved.





Design of SG-III Laser Facility – Optical layout of FOA

Research Center of Laser Fusion CAEP



- Type I+Type II+Type II design for Frequency converter to match 1.2nm band width of pulse
- Two kind of diffractive element (BSG,CPP) is designed.
- BSG: to sample 3w beam for Energy and temporal shape measurement
- CPP: to shape the intensity distribution of focal spot.




Design of SG-III Laser Facility – Optical layout of beam smoothing



Research Center of Laser Fusion CAEP

Beam smoothing






Design of SG-III Laser Facility – Front end



Research Center of Laser Fusion CAEP

- ✓ Pulse rise time: <100ps
- ✓ Pulse width: 1.0ns~6.0ns
- ✓ arbitrary shaped
- ✓ Pulse contrast: 80:1
- ✓ Spectral width: ~1.2nm
- ✓ Pulse SRN: >45dB
- ✓ Pulse energy: 10.0 μ J/1Hz/beam
- ✓ Energy spread: <2.0%(RMS)
- ✓ Synchronization: ≤2.0ps(RMS)

- Three kind of pulse(fs/ps/ns) can be generated without time jitter.
- Realize pulse shaping and long /short pulse synchronizing without time jitter based on optical method
- All fiber system.






Design of SG-III Laser Facility –Preamplifier


Research Center of Laser Fusion CAEP



- ✓ Energy: 5J/3ns/beam/20min, 100mJ/beam/1Hz
- ✓ Pulse width: 1.0ns~10.0ns
- ✓ Beam spatial distribution : super gauss
- ✓ Modulation: $\leq 1.4:1$
- ✓ Beam divergence : $\leq 150 \mu\text{ rad}$
- ✓ Energy stability: $\leq 4.0\%(\text{RMS})$
- ✓ Spectral width: 1.2nm
- ✓ Beam drift: $\leq 10 \mu\text{ rad}(\text{RMS})$ (4 hours)



➤ Liquid crystal is used to shape the output spatial distribution of beam and compensate the gain non-uniformity of disk amplifier
➤ Whole image relay design





Design of SG-III Laser Facility – Disk Amplifier

Research Center of Laser Fusion CAEP



- ✓ Clear aperture: $400 \times 400\text{mm}^2$
- ✓ Storage density: $\rho_{st} \sim 0.24\text{J/cm}^3$
- ✓ $g:$ $5.0\%\text{cm}^{-1}$ (thickness:40mm)
- ✓ gain uniformity : $\beta_{peak} / \beta_{ave} \approx 1.08:1$
- ✓ Storage efficiency: $\eta_{st} > 3.0\%$
- ✓ Static wavefront distortion: $< \lambda / 3/\text{disk}$ ($\lambda = 632\text{nm}$)
- ✓ Shot interval: <4 hours




- Water cooling design is considered.
- Performance of disk amplifier is undergoing validated, especially the gain non-uniformity and thermal distortion





Design of SG-III Laser Facility – PEPC of large aperture

Research Center of Laser Fusion CAEP



- ✓ Clear aperture: $400\text{mm} \times 400\text{mm}$
- ✓ Wavelength: $1.053 \mu\text{m}$
- ✓ Static transmission: $\geq 88\%$
- ✓ Isolation ratio: $\geq 200:1$
- ✓ Switch efficiency: $\geq 99\%$
- ✓ Switch rise time: $\leq 200\text{ns}$
- ✓ Switch time window: 600ns

Single pulse drive mode.






Design of SG-III Laser Facility -----Structure of laser area

Research Center of Laser Fusion CAEP




SG-III Laser Facility
Structure Design
(laser experiment
area)





Design of SG-III Laser Facility ----- Structure of beamline


Research Center of Laser Fusion CAEP





Design of SG-III Laser Facility -----Structure of beamline


Research Center of Laser Fusion CAEP





Design of SG-III Laser Facility ---- Structure of laser area

Research Center of Laser Fusion CAEP



Cavity transfer SF


Measurement unit.

Pre-amp. system

Design of SG-III Laser Facility ---- Structure of target area




Research Center of *Laser Fusion* CAEP



Design of SG-III Laser Facility ---- Structure of switchyard




Research Center of Laser Fusion CAEP



Design of SG-III Laser Facility ---- Structure of switchyard



Research Center of Laser Fusion CAEP



Outline



Research Center of Laser Fusion CAEP




◆ **Introduction**

◆ **Design of SG-III Laser Facility**

◆ **Status of SG-III Project**


◆ **Summary**



Status of SG-III Project –Schedule



Research Center of Laser Fusion CAEP






Status of SG-III Project – Laser house

Research Center of Laser Fusion CAEP



The laser house are being constructed and will be completed in the end of June, 2009



Laser hall




Shear wall in laser hall



Target area



Status of SG-III Project – Engineering design



The detailed engineering design has been finished before May, 2008, the main manufacturer for key unit and vendor for optics material have been selected.




Status of SG-III Project – Performance test of key unit and module


Research Center of Laser Fusion CAEP





Front end



Rise time less than 100ps



Contrast 1:80



Different kind of shaped pulse

Main units in Front end were validated and can meet the requirement of design.



Status of SG-III Project – Performance test of key unit and module

Research Center of Laser Fusion CAEP



The installation of $4 \times 2 \times 3$ disk amplifier In July,2008,



Overview of the $4 \times 2 \times 3$ disk amplifier performance testbed



Disk Amplifier



Flash lamp module



Nd glass



Energy bank

Installation of $4 \times 2 \times 3$ Disk Amplifier Module was completed, and performance experiment including gain measurement are started.

Outline



Research Center of Laser Fusion CAEP




◆ **Introduction**

◆ **Design of SG-III Laser Facility**

◆ **Status of SG-III Project**

◆ **Summary**





Summary

Research Center of Laser Fusion CAEP



- 1. Experiment results demonstrated the main specifications of the TIL ,the prototype of SG-III, have been reached, the first round of physics experiment shows that TIL has the capability to provide shots for experiment.**
- 2. The detailed design of SG-III has been finished and the fabrication plan has been started.**
- 3. Experiment to validate performance of key unit such as amplifier, front end, pre-amplifier are being carried out.**



Research Center of Laser Fusion CAEP



Thanks for attention!